

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

✓
LAND CORNER RECORD

T. 21 N.R. 5 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 14, 23

CORNER MONUMENT Set Cons. Dept. monument

DATE MONUMENT PLACED AND WITNESSED 8/17/67

WITNESSES TO CORNER.....



7" R. Oak S 23 W 16.5'

8" R. Oak S 70 E 34.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a partial retracement of this township. Found pipe as previously established in 1934 survey by Marcus Schaaf. One U.S.B.T. stamp in place SW. Falls very nearly on line and midpoint between section corners.

SURVEYOR'S SEAL

SIGNED Kenneth J. Dittling DATE 8/28/67
REGISTERED LAND SURVEYOR 420068