

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>MISSAUKEE</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>5W</u>	<u>G-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T <u>21N</u> R <u>5W</u>	<u>7, 9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S <u>4</u> T <u>21N</u> R <u>5W</u>	<u>**658.1-W OF COR</u>
	S _____ T _____ R _____	<u>CODE 7</u>

*filed  
8/17/82*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on FEBRUARY 3, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

~~C. CONTINUED. Description of monument and accessories established to perpetuate locating the position of the corner:~~

DRIVE 5/8" X 34" REROD W/RLS CAP.  
 SET CED POST W/LOC TAG.  
 5" MAPLE N35°E 21.8'  
 9" R PINE S23°E 9.2'  
 3" OAK S50°W 8.4'  
 CTR TRAIL DUE S 269'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 G-2 FD & ACCEPTED 1 1/4" PIPE FOR E 1/4 COR S-4. PIPE FITS Y.PINE STP. REMAINS; N55°E, 4.0' PER U.S. GLO 1852 RESURVEY NOTES. M.SCHAAF HAD THIS COR ALSO, IN 1938.  
 7 ESTAB'D NE COR OF E 1/2- SE 1/4-NE FRAC 1/4 S-4, PER STANDARD BLM INSTRUCTIONS.  
 9 ESTAB'D NE COR OF NW 1/4 - SE 1/4 S-4, PER STANDARD BLM INSTRUCTIONS.  
 \* ESTAB'D NW COR OF E 1/2-SE 1/4-NE FRAC. 1/4 S-4, PER STANDARD BLM INSTRUCTIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>G-2</u>	<u>7</u>	<u>9</u>
FD 1 1/4" PIPE; SET CED POST W/LOC TAG.	DRIVE 3/8"X5 1/2' GALV PIPE W/ RLS CAP. SET CED POST W/LOC TAG	DRIVE 5/8"X34" REROD W/RLS CAP & SET CED POST W/LOC TAG.
9" OAK N35°W 9.6'	6" ASH N62°W 13.4'	10" MAPLE S70°E 4.6'
3" OAK N72°E 12.9'	12" CEDAR N50°E 29.0'	10" MAPLE S62°W 4.7'
8" OAK S08°E 47.7'	9" CEDAR S72°W 24.4'	5" MAPLE N54°W 3.3'
5" BALSAM S40°W 11.3'	S'LY EDGE SWP DUE S 430'±20'	

Signed by Carl F. Roser 10-25-88 Date \_\_\_\_\_  
 Surveyor's Michigan License No. 12028

