

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MISSAUKEE
 (County)

Located In: _____ Corner Code #/

1. Public Land Survey	T	<u>21N</u>	R	<u>5W</u>	<u>J-13, K-12</u>
	T	_____	R	_____	<u>K-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	<u>35</u>	T	_____	<u>16</u>
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL F. ROSER, in a field survey on NOVEMBER 11, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>J-13</u>	<u>K-12</u>	<u>K-13</u>	<u>16</u>
		(*B* CONTINUED)	
		COR ALSO FALLS ON LINE ACROSS	
		FD LAPHAM'S NW S-1 AND S 1/4	
		S-36.	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>J-13</u>	<u>K-12</u>	<u>K-13</u>	<u>16</u>
SET DNR MON MIDWAY & DN LINE BETWEEN FD SW COR SEC. 35 & ESTABLISHED SE COR SEC 35; FOR S 1/4 COR SEC 35.	SET 5/8" REROD FOR E 1/4 COR SEC 35 MIDWAY & ON LINE BETWEEN FD NE COR SEC 35 & REESTABLISHED SE COR SEC 35. CTR OF 18' WIDE N-S- DIRT ROAD 16 11' EAST.	DR 5/8" REROD W/L.S. CAP FOR SE COR S-35. COR SET ON AVG LINE OF OLD FIELD BERM W/ BURIED WIRE (E-W), LOOKING E'LY; & AT PROP MEAS (RUN-OUT) W OF P. LAPHAM (1983) NW S-1, T20N-R5W, (PROP. GLO TO S LINE SEC'S 35 & 36, T21N-R5W); 806.25' MEAS & 811.1' = U.S. COR IS 11'± N & 38'± W OF INTER OF SAND RDB N-S-W & NE'LY. (CONTINUED IN "A")	DROVE 5/8" REROD W/L.S. CAP FOR SE COR OF W 1/2 OF SE 1/4 OF SEC 35. COR SET PER STANDARD BLM INSTRUCTIONS. COR BURIED AT SOUTH EDGE OF E-W (GRADED) SAND ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>J-13</u>	<u>K-12</u>	<u>K-13</u>	<u>16</u>
SET DNR MON & CED POST. 10" R PINE N 3°W 166.0' 2" OAK N65°E 37.5' 1" OAK S35°E 75.2' 3" OAK S55°W 38.0' CTR E-W WINDING SAND RD DUE N 132' CTR SAND TRAIL TO SOUTH DUE E 59'±2'	SET 5/8" X 17" REROD W/RLS CAP OVER 5/8" X 34" REROD. SET CED POST W/LOC TAG. 7" OAK N45°W 31.8' 7" R PINE N40°E 61.5' 7" R PINE S60°E 46.8' 9" OAK S40°W 8.2'	DR 5/8" X 34" REROD W/RLS CAP. 4" OAK N70°W 69.6' 3" OAK (CLP 3) N40°W 78.0' 3" OAK S10°E 75.7' 3" OAK S20°W 64.9' FD 1 1/2" PIPE IN 6" X 6" X 6" CONC BLK S40°43'E 65.32' FB 2" PIPE, SIGN POST BOTTOM N71°25'E 13.73' SET CED POST W/TAG DUE N 33'	DROVE 5/8" X 34" REROD W/RLS CAP. 10" R PINE N30°E 69.0' 8" R PINE N60°E 55.4' 2" OAK S20°E 11.4' SET CED POST W/ LDC TAG. DUE N 33'

Signed by Carl F. Roser 5-22-92 Date _____
 Surveyor's Michigan License No. 12028

