

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MILWAUKEE
(County)

Located In: _____ Corner Code ~~##~~

- | | | |
|------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey | T <u>21N</u> R <u>5W</u> | <u>L-13, M-11</u> |
| | T _____ R _____ | <u>M-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CARL F. ROSER, in a field survey on JULY 26, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 L-13 M-11 M-12

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- | | | |
|---|--|---|
| L-13
FD 1/2" REROD FOR S 1/4 COR SEC 36 AS ESTABLISHED BY L.S. P. LAPHAM. E-W BERM, W/CEDAR FN POSTS & WIRE REMAINS, IS SOUTH 18'±. | M-11
FD 1 1/2" PIPE FOR NE COR SEC 36 AS SET BY M. SCHAAF. COR FITS U.S. GLO TIES TO BAYOU S. (US=80', WE MEAS 89'±) AND W (US=188', WE MEAS 183'±) CLOSE. | M-12
SET DNR MON MIDWAY & ON LINE BETWEEN FD SEC COR'S 1/2 MILE N & S; FOR E 1/4 COR SEC. 36. |
|---|--|---|

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|--|---|
| L-13
FD 1/2" X 18" REROD W/RLS CAP; ADDED DNR MON & SET CED POST.
+12" J PINE N65°W 20.48
+ 5" J PINE N 5°E 24.64
9" MAPLE S60°E 44.25
8" TW MAPLE S20°W 51.35
W'LY EDGE
MUSKEGON RVR DUE E 244±3' | M-11
DROVE 1" X 8" GALV PIPE W/ALUM DNR CAP IN FD 1 1/2" X 3 1/2" BLK PIPE; & SET WOLMANIZED PINE POST.
7" ASH N55°W 10.0'
12" & 8" MAPLE N70°E 10.2'
8" MAPLE S35°E 28.3'
7" MAPLE S60°W 2.2' | M-12
SET DNR MON & CED POST.
5" MAPLE (CLP 3) N70°E 13.8'
11" OAK S10°W 6.2'
5" BALSAM S40°W 23.4'
3" TW MAPLE N60°W 8.6'
W'LY EDGE
MUSKEGON RVR DUE S 211±3' |
|---|--|---|



Signed by Carl F. Roser

Date 5-22-92

Surveyor's Michigan License No. 12028