

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MISSAUKEE
 (County)

Located In: _____ Corner Code ~~##~~

- | | | | | | |
|------------------------------------|---|------------|---|-----------|----------------------|
| 1. Public Land Survey | T | <u>21N</u> | R | <u>5W</u> | <u>K-7, K-8, K-9</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL F. ROSER, in a field survey on FEBRUARY 14, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-7	K-8	K-9
-----	-----	-----

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<p>K-7 FD DEPT MON FOR NE COR SEC 23, MON SET BY K. OSTLING IN 1967 DEPT SURVEY AT LOCATION OF FD PIPE IN CONCRETE AT POINT PRESCRIBED BY WITNESSES OF RECORD FROM EARLY SURVEY BY COUNTY SURVEYOR. COR IS BURIED IN APPROX CTR N-S SAND TRAIL. TRAIL RD WEST IS 98'± SOUTH. COR IS IN LINE WITH BERM, W/WIRE ON GROUND TO WEST.</p>	<p>K-8 REESTABLISHED E 1/4 COR OF SEC. 23 FROM TWO FOUND KEN OSTLING WITS (OAK S60°E, 40.0' FD OK AND J. PINE N65°W, 23.3', FOUND STUMP). OSTLING SET COR AT MIDPOINT AND ON LINE BETWEEN SECTION CORNERS. COR FALLS AT N EDGE N-S SAND TRAIL.</p>	<p>K-9 FD DEPT MON FOR SE COR SEC 23 AS SET BY K. OSTLING IN 1967 SURVEY. OSTLING FOUND OLD STAKE POINT & WITNESSES BY CO. SURVEYOR MCBAIN. CTR OF N-S TRAIL IS 6'E. FD 1" SQ BY 16" IRON S72°37'E, 20.12'.</p>
---	---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>K-7 FD DNR MON. 10" B. OAK N78°E 49.5' #11" TM B OAK S42°E 58.6' B" TM B OAK S34°W 58.5' #18" B OAK N58°W 51.2' SET CED POST W/ LOC TAG. WEST 33' #KJO 1967 WIT.</p>	<p>K-8 DROVE 5/8" X 3/4" REROD W/RLS CAP FROM 2-KJO WITS. 13" OAK N38°E 56.5' #11" DAK S63°E 40.0' 13" OAK S70°W 74.0' SET CED POST W/LOC TAG. WEST 33' #KJO 1967 WIT.</p>	<p>K-9 FD DEPT MON (BURIED 6") AT W EDGE OF N-S TRAIL RD. 9" R PINE N32°W 34.6' #14" J PINE N67°E 36.8' 14" TM OAK S38°E 48.3' 7" R PINE S27°W 44.6' #10" J PINE N61°W 14.6' SET CED POST W/ LOC TAG. WEST 33.4' #KJO 1967 DEPT WIT.</p>
---	---	---



Signed by Carl F. Roser 12028 Date 5-22-92

Surveyor's Michigan License No. _____