

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Missaukee Located In _____ Corner Code # _____
 (County)

- | | | | | | | |
|--------------------------------------|---|-------|---|-------|---------|-------|
| 1. Public Land Survey | T | 21N | R | 5W | MC 31 | |
| | T | _____ | R | _____ | 1 | _____ |
| 2. Property Controlling in Section | S | T | R | _____ | _____ | _____ |
| | S | T | R | _____ | _____ | _____ |
| 3. Miscellaneous Property in Section | S | T | R | _____ | _____ | _____ |
| | S | T | R | _____ | _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Nov. 3, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3			2	1
3													
4	7			8		9			10			11	12
5													
6	18			17		16			15			14	13
7													
8	19			20		21			22			23	24
9													
10	30			29		28			27			26	25
11													
12	31			32		33			34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| MC 31 - GLO - West on S. side Sec. 31, T21N, R5W
 1 79.50 CH. Inter. E. Margin Lake. Set Post - J. Brink - 1837
Tamarack 6" N54°E 99 L.
Tamarack 6" S84½°E 210 L.
82 CH. To Twp. Cor. in Lake
- GLO - Resurvey - M. Nye - 1857
West 13.50' CH. from post corner of T20N, R5 & 6W
Intersected E. Margin at Lake - Set Post
Tamarack 6" N54°E 99
Tamarack 6" S84½°E 210
- M. Schaaf - 1938 - Notes Indicates corner set.
- LCRC - L. 2, P. 727 - C. F. Roser - 1987 | USMC 167' E of 'A13' - Fd. 1 ½" pipe rotted off as set in 1938 by M. Schaaf for US meander corner on W. end of S. line of Sec. 31, T21N, R5W. Corner is 167' East of Calc. Twp. Corner to T21N, R5-6W in Lake. U.S. calls for 165'. The Cranberry bog is open one can see 1000'± in any direction from this corner except that this corner falls at SE'ly corner of approx.'ly 300'± x 300' stand of Tamarack and Tag Alder. Added 1 ½" x 10 ½' pipe w/ Alum. DNR Cap and Cedar post w/ Loc. tag in Cranberry Bog w/ standing water.
9" Tamarack N72°W 110.4'
8" Tamarack N40°W 91.4'
2" Tamarack N20°E 43.3'
E'ly edge Lake Due W. 125' ± 5' |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- MC | 31 Meander corner on E. side of Cranberry Lake between Sec. 31, T21N, R5W and Sec. 1, T20N, R6W - Fd. 1 ½" pipe next to
 | 1 rusted off 1 ½" pipe per Roser - below 1' of water in bog. Fd. 2 dead Roser Tam. BT's. Dead Tam. At N40°W 91.4' OK but dead Tam @ N72°W measured 107.3' not 110.4'. 1 ½" iron pipe accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- MC | 31 - Drove stamped 2" Alum. Cap on 5/8" x 5' long rebar into 1 ½" iron pipe - Up 1.3'
 | 1 Set Blue Carsonite Post 1' N.
 N43°W 33.25' to set N & T in NE side 4" Tamarack
 N19°E 36.65' to set N & T in E side 3" Tamarack
 East 25.0' to set ½" x 16" rebar
 S9°W 15.0' to set ½" x 16" rebar
 West 167' (166.98' - Grid) to Calc. position of Twp. Cor. T21N, R5-6W in Lake.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 3/7/2005