

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Misaukee Located In _____ Corner Code # _____
 (County)

- | | | | | | |
|--------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | 21N | R | 5W | J11 |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | T | R | _____ | _____ |
| | S | T | R | _____ | _____ |
| 3. Miscellaneous Property in Section | S | T | R | _____ | _____ |
| | S | T | R | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct. 5, 2009 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11									●				
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J11 - 1852 - GLO - A. Curtis - Set 1/4 Post
 1) S. Pine 8" S50°E 48 L.
 2) S. Pine 6" N12°W 29 L.
 - 1915 - CSR - FB #39, p. 71 & 79 - Sec. 26 Survey
 OB Stps. OK. 3) P. Pine 6" S5°E 35
 4) P. Pine 8" S64°W 22
 Distance W. 40.05; E. 40.40; N. 79.64

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J11 - 1/4 Corner common to Sec. 26 & 35, T21N, R5W - Recovered corners 'J9' and 'J10' per County Survey Records. It appears that 'J10' was set midway between 'J9' and 'J11'. Thus at doubled distance and line south from 'J9' through 'J10' dug 9' N & S by 4' wide area in existing N-S sand road searching for evidence of stake or any monument but nothing was found. Witnesses #1 through 4 are gone. Set DNR Monument by doubling line & distance south from 'J9' through 'J10' - Grid distance is 5261.92' vs. 5256.24' - CSR to 'J9'. Measured south from 'J11' - 1319' to apparent PI of Sand 2-Track N & W. DNR Monument falls in centerline of N-S Sand Rd. DNR Monument accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J11 - 4" DNR Alum. Cap on 1" x 36" galv. iron pipe with 4" x 1' long PVC filled with concrete around cap - 0.6' below grade.
 Set Blue Carsonite Post with loc. Tag 33' East
 N27°W 40.87' to set N & T in E. side 5" J. Pine
 N48°E 47.71' to set N & T in NW side Tw. 12" and 9" R. Pine scribed 'XBT'
 S29°E 50.80' to set N & T in E. side 10" W. Oak
 S57°W 21.47' to set N & T in N. side 7" Oak scribed 'XBT'



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 4/5/2010