

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Missaukee Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 14 T 21N R 6W 5
S 14 T 21N R 6W 6

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on Aug. 20, 2014 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

5 – 2003 – Record Surveys – L. S-4, P. 199, P. 201 & P. 209 – D. E. Schripsema (PS #24617) – Set iron

6 – 2003 – Record Surveys – L. S-4, p. 199 & P. 209 – D. E. Schripsema (PS #24617) – Fd. iron

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

5 – CN 1/16 Corner Sec. 14 – Fd. Loose 1/2" x 18" rebar in leather leaf marsh. Iron fits Schripsema E-W line of monumentation per record surveys. 1/2" rebar is S39°29'W 0.80' from calculated position. Accepted 1/2" x 18" rebar as the best available evidence of the position of the corner.

6 – NE 1/16 Corner Sec. 14 – Fd. 1" O.D. iron pipe – Up 0.4'- of unknown origin used by Schripsema in his surveys. Pipe is S39°34'W 1.7' from calculated position for corner. Based on usage accepted 1" pipe as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 – Replaced 1/2" x 18" rebar with Stamped 2" Aluminum Cap on 5/8" x 4' long iron rebar.
Set Blue Composite Post with loc. tag 1' South
S22°E 22.29' to set 1/2" x 18" rebar
S74°W 29.81' to set 1/2" x 18" rebar
N2°W 60.06' to set N & T in W. side 6" W. Pine
N54°E 57.19' to set N & T in NW side 6" J. Pine

6 – Set stamped 2" Aluminum Cap on 5/8" x 15" rebar in center of existing pipe. Add ring of stones.
Set Blue Composite post with Loc. tag 1' SE
S65°W 10.94' to set N & T in S. side Tw. 12" Oak
N7°E 10.17' to set N & T in E. side 16" Oak
S76°E 9.87' to set N & T in N. side 11" R. Maple
S1°W 22.87' to set N & T in E. side 13" R. Maple

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 1/15/2015

