

SURVEY & REMONUMENTATION

APR 24 1995

LIBER 291 PAGE 431

980

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

	<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey		T <u>21N</u> R <u>6W</u>	<u>B-13</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 23 1995 12:01 PM

Carlyne Flare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13) 1837 GLO post by John Brink, Deputy Surveyor
Beech 10 N 17 1/2 W 22,
Sugar 10 N 51 1/2 E 47

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13) Quarter corner, Section 31, T21N, R8W and Clare County

Found 1/2" Iron and it is accepted as a careful and faithful reestablishment of the position of the original corner. No previous record as to the origin of the Iron could be located.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


B-13) Set 2 1/2" brass Missaukee County monument on existing Iron

S 51 E 46.58 Power Pole
N 58 E 54.59 Telephone pedestal
N 34 W 39.93 Cor. Fence post
S 82 W 92.38 Mail Box post

Centerline road intersection, trail to north

Peer Group Reviewed and Approved
Date: 11-2-94
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema
Surveyor's Michigan License No. 24617



Date 12-30-94