

**SURVEY &
REMONUMENTATION**

LIBER 291 PAGE 430

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

979

For corners **COMMISSION**
Missaukee
(County)

Located In: **21N 6W** Corner Code # **C-13**

1. Public Land Survey T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

MISSAUKEE COUNTY MICHIGAN
RECORDED **JAN 23 1995 12:01 PM**
Carlynn Flare
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel E. Schripsema a field surveyor on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-13) 1837 GLO post by John Brink, Deputy Surveyor
Birch 14 N 78 W 20, Cedar 10 N 72 E 25

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-13) Section corner common to Sections 31 and 32
Reset 1/2" iron/cap at fence intersection North, East & West per Porter unrecorded survey. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-13) Set 2 1/2" brass Missaukee County monument on reset iron.

N 78 E 48.65 12" cedar
N 36 W 12.67 15" cedar
N 74 W 36.88 10" cedar
S 21 E 18.36 12" cedar

Peer Group Reviewed and Approved
Date: 12-2-94
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema
Surveyor's Michigan License No. 24617



Date 12-30-94