

JAN 19 2000

LIBER 333 PAGE 440

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1352

For corners in

<u>Missaukee County</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>06W</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 09 1999 4⁰⁰ PM

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, J. Dean Geers, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-8) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor. 10" White Ash-S18W-33 lks, 10" Beech-N67W-48 lks.
- M-8) 1901 Teed notes: Found W. Ash - southwest ok and rotten roots of Beech northwest. Lynn 30-S28 1/4 E-13 lks, Sugar 24-N74W-62 1/2 lks.
- M-8) 1987 Roser survey and LCRC; Liber 1, Page 750; Set DNR monument and Cedar post. 9" Maple-N24E-31.1', 16" Maple-N84E-46.0', railroad tie fence corner post (East and North)-S45E-10.45', 2" White Birch-S30E-31.2'. Re-established corner equidistant and on line between northeast and southeast corners of Section 24.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-8) Quarter section corner common to Section 24, T21N, R6W and Section 19, T21N, R5W. Found DNR monument and cedar location post as recorded in Liber 1, Page 750. Corner is in fenceline east and west, and ± 1' east of fenceline north. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8) Found DNR Monument

East	35.96'	Set nail in south face of 10" oak
*N30E	31.60'	Set nail in east face of 10" maple
S35E	31.30'	Set nail in west face of 3" white birch
S62W	6.92'	Set nail in southeast face of 10" poplar
West	±17.7'	Centerline of Trail
*East	46.0'	±16" stump

*Previous Witness



Peer Group Reviewed and Approved

Date: 12-9-99
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977

Date 11-23-99