

JAN 19 2000

LIBER 333 PAGE 442

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

#1355

Form with fields for Missaukee County, Located In: T 21N R 06W, Corner Code # M-11, and sections 1-3 for Public Land Survey, Property Controlling, and Miscellaneous.

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 09 1999 4:00 PM

Signature of Carolyn Florie, Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, J. Dean Geers, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numbers 6 through 36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of monuments including M-11) 1837 GLO Section Corner Post by John Brink, M-11) 1852 GLO Section Corner Post recovered by A. Curtis, M-11) 1938 Schaaf notes; Found post. Set monument, and M-11) 1987 Roser survey and LCRC; Liber 1, Page 730; Found 1 1/2" pipe set by Schaaf from USBT stumps, added Cedar post with location tag.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11) Section corner common to Section 25, T21N, R6W, Section 36, T21N, R6W, Section 30, T21N, R5W, and Section 31, T21N, R5W. Found 1 1/2" pipe and cedar location post as recorded in Liber 1, Page 730. This corner is accepted as a careful and faithful perpetuation of the position of the original corner. Possible GLO witness: S25W 10.7' Face of +/- 15" old stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11) Found 1 1/2" pipe and drove 5/8" x 36" rebar into pipe and set Missaukee County Monument.
N22W 21.72' Set nail in southwest face of 8" maple clump
S78W 18.23' Set nail in north face of 8" white pine
S75E 5.65' Set nail in south face of 6" white pine
S20W 60.60' Set nail in east face of 16" twin oak
\*N48W 19.0' 30" oak deadfall
\*N63E 5.2' 8" oak deadfall
\*S26W 58.5' 18" oak with blaze (dead)

\*Previous Witness



Peer Group Reviewed and Approved

Date: 10-9-99
J. Dean Geers, Missaukee Co. Representative

Signed by [Signature]
Surveyor's Michigan License No. 33977

Date 11-23-99