

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____
 Missaukee _____
 (County) _____

Located In _____

Corner Code # _____

1. Public Land Survey		T	<u>21N</u>	R	<u>6W</u>	<u>L8</u>
		T	<u>21N</u>	R	<u>6W</u>	<u>L10</u>
2. Property Controlling in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____
3. Miscellaneous Property in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Dec. 2, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L8 - None

L10 - Rec. Sur. - L. S-3, p. 237 -
 D. E. Schripsema - 1994 - Set iron

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L8 - C 1/4, Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" iron Rebar at intersection of 1/4 lines per standard BLM procedure.

L10 - C 1/4, Sec. 25 - Fd. 1/2" x 18" capped iron rebar #24617 per record survey a N. Edge of swamp. 2-track is 242' North. 1/2" CIR accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L8 - Stamped 2" Alum. Cap on 5/8" x 34" rebar
 Set Blue Carsonite Post 2' SE
 S45°W 61.42' to set N & T in SE side 7" R. Maple
 N64°W 52.08' to set N & T in S. side 23" W. Pine
 N24°E 21.52' to set N & T in W. side 6" R. Maple
 N80°E 12.7' to set N & T in S. side 4" W. Pine

L10 - Replaced 1/2" CIR with stamped 2" Alum. Cap on 5/8" x 34" rebar
 Set Blue Carsonite Post 1' SE
 N65°W 31.92' to set N & T in SW side 5" R. Pine
 N13°W 32.80' to set N & T in E. side 11" J. Pine
 N29°E 62.18' to set N & T in NW side 8" Oak
 N63°E 36.62' to set N & T in NW side 13" J. Pine

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 3/7/2005

