

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____
 Missaukee _____
 (County) _____

		Located In		Corner Code #
1. Public Land Survey		T _____	R _____	_____
		T _____	R _____	_____
2. Property Controlling in Section	S 24	T 21N	R 6W	6
	S 24	T 21N	R 6W	9
3. Miscellaneous Property in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Dec. 6, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
6 - None 9 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

6 - NE 1/16, Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" rebar per standard BLM procedure.

9 - CE 1/16, Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
 N63°E 55.95' to set N & T in N. side 14" R. Pine
 S30°E 3.30' to set N & T in E. side 16" R. Pine
 S58°W 35.55' to set N & T in N. side 4" Oak
 N20°W 46.07' to set N & T in W. side 10" J. Pine
 Set Blue Carsonite Post with Loc. Tag 1' NW

9 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
 N18°W 42.90' to set N & T in W. side 6" R. Maple
 N60°E 36.84' to set N & T in SE side Tw. 10" R. Maple
 S32°E 30.39' to set N & T in NE side 12" R. Maple
 S26°W 32.89' to set N & T in W. side 4" R. Maple Clp. - 6
 Set Blue Carsonite Post w/ Loc. Tag 1' NW

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 3/7/2005

