

SURVEY & REMONUMENTATION

DEC 21 1993

895

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 338

For corners in

| Missaukee (County) | Located In: | Corner Code # |
|------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>21N</u> R <u>7W</u> | <u>A-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 13 1993 11:43 AM

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, J. Dean Geers, in a field survey on December 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-13) 1837 GLO post by John Brink, Deputy Surveyor
Lynn 16 N 67° W 20, B. Ash 10 N 32° E 36
- A-13) Beuthien Notes: Stone, Maple 7 N 57 1/2° E 44, Elm 12 N 82 1/2° W 2.40
- A-13) 1986 McClung survey, Liber S-2, page 312: Corner was used, no information given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-13) Section corner common to Section 31, T21N, R7W and Section 36, T21N, R8W
Found 1/2" Iron in centerline of trail to North and on North edge of East-West two-track. No record as to the origin of the Iron could be located. The corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-13) Set Missaukee County monument on existing Iron
Corner is ±6" below the road surface
S 67° E - 53.73 - Set pk in South end of cross-culvert
S 71° W - 81.69 - 4" Cedar
N 57° W - 35.40 - 4" B. Ash
N 18° W - 50.05 - 4" B. Ash

Peer Group Reviewed and Approved

Date: 12/8/93
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/8/93
Surveyor's Michigan License No. 33977