

SURVEY & REMONUMENTATION

DEC 21 1993

#897

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 340

For corners in

Form with fields for Missaukee (County), Located In, Corner Code #, and numbered items 1-5 for Public Land Survey, Property Controlling, etc.

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 13 1993 11 A.M. 30

Handwritten signature: Evelyn Flare

Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-12, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

C-13) 1837 GLO post by John Brink, Deputy Surveyor Hemlock 12 N 69 1/2° E 28, Hemlock 14 N 81° W 25

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13) Reestablished Section corner common to Sections 31 and 32 on line and at proportional distance between the Southwest corner of Section 31 and the South 1/4 corner of Section 32. The corner falls ±16' North of the East-West fence line and ±13' West of the North-South fence remains. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13) Set 1/2" x 36" Iron and Missaukee County monument

N 38° E - 32.29 - 10" Balsam
S 11° E - 35.82 - 6" Balsam
S 70° W - 12.11 - 8" Poplar
N 15° W - 7.16 - 3" Balsam

Peer Group Reviewed and Approved

Date: 12/8/93
J. Dean Geers, Missaukee Co. Representative

Signed by [Signature] Date 12/8/93
Surveyor's Michigan License No. 33977