

DEC 27 1993

COMMISSION

#910

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 436

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>7W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 16 1993

Paulyn Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13) 1837 GLO Section post by John Brink, Deputy Surveyor
Hemlock 13 N 37° E 13, Hemlock 16 N 61 1/2° W 43

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13) Reestablished the Section corner common to Sections 32 and 33 on line and at proportional distance between the South quarter corner of section 32 and the Southeast corner of section 33. Corner falls ±16' North of old East-West fence and ±1' East of old North-South fence. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13) Set 1/2" x 36" Iron and Missaukee County monument

- S 79° E - 15.12 - 6" Maple
- S 15° E - 18.49 - 4" Balsam
- N 88° W - 34.05 - Twin 14" White Birch
- N 58° W - 45.16 - 8" Cedar

Peer Group Reviewed and Approved

Date: 12-15-93

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/15/93

Surveyor's Michigan License No. 33977