

**SURVEY & REMONUMENTATION**

DEC 21 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

# 899

LIBER 383 PAGE 342

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>7W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 13 1993 11:30 A.M.

*Paulyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on December 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor  
Cottonwood 16 N 55° E 09, B. Ash 10 N 29° W 28

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13) Reestablished the South Quarter corner of Section 33 on line and at proportional distance between the South Quarter corner of Section 32 and the Southeast corner of Section 33. Corner falls ±31' East of fence to North and ±7' South of East-West fence. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13) Set 1/2" x 36" Iron and Missaukee County monument

N 45° E - 18.95 - 16" B. Ash  
S 14° W - 36.33 - Twin 4" Cedar  
S 57° W - 61.42 - 6" Cedar  
N 71° W - 46.95 - 14" B. Ash

Peer Group Reviewed and Approved

Date: 12/8/93

*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*

Date 12/8/93

Surveyor's Michigan License No. 33977