

SURVEY & REMONUMENTATION

DEC 21 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

900

LIBER 283 PAGE 34

For corners in

Missaukee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 21N R 7W G-13
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 13 1993 1/A

Paulyn Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, J. Dean Geers, in a field survey on December 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13) 1837 GLO post by John Brink, Deputy Surveyor
White Pine 17 N 49° E 25, Maple 12 N 45 1/2° W 71
- G-13) 1912 Beuthien survey in Section 34: Stone perpetuated by Richardson, Apple 5 N 66° W 218
- G-13) 1982 McClung LCRC, Liber 1, page 677: Found 1 1/4" pipe in fence line running West
- G-13) MDOT M-66 Right of Way sheet 57-R-2: Corner is indicated

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13) Section corner common to Sections 33 and 34:

Found 1 1/4" pipe in fence line running West and in centerline of road to North. Corner is ±9' North of East-West field lane. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13) Found 1 1/4" pipe which had been recently hit and bent.
Replaced pipe with 1/2" x 36" Iron and Missaukee County monument at original location

- N 87° W - 21.00 - Fence post
- N 22° E - 67.34 - Set Iron at the end of guy wire
- N 41° E - 79.58 - Power pole
- S 05° W - 9.13 - Set Iron in centerline of East-West field lane

Peer Group Reviewed and Approved

Date: 12/8/93

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/8/93
Surveyor's Michigan License No. 33977