

DEC 21 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 344

901

For corners in

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 7W	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 13 1993 11:30 AM

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, J. Dean Geers, in a field survey on December 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor
Aspen 10 N 79° E 11, Maple 12 N 78 1/2° W 22
- H-13) 1912 Beuthien Survey: perpetuated by Richardson, Iron pipe, fence post S 80 1/2° E 238
- H-13) 1993 Granger Survey, Liber S-3, page 179: Set Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-13) South Quarter corner of Section 34
Found Iron of record per S-3, page 179 and was not utilized in this survey.

Restored the South Quarter corner of Section 34 from the fence post wit. per the Beuthien survey and 33' South of the base of the corner fence post to the North. The corner falls in the centerline of the East-West road and ±1' East of the fence to the North. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-13) Set 1/2" x 18" Iron and Missaukee County monument
N 35° W - 70.72 - clump Thorn Apple
N 09° W - 33.03 - Set Iron at base of old corner fence post
N 82° E - 45.46 - Found Iron set by Granger Associates
S 08° W - 23.22 - Set Iron @ back of ditch opp. fence to North
S 80° E - 157± - Base of old corner fence post

Peer Group Reviewed and Approved
Date: 12/8/93
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/8/93

Surveyor's Michigan License No. 33977