

JAN 13 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 333 PAGE 414

For corners in

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T 21 N R 7 W	1-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

# 1326

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 09 1999 3:55 PM

*Carolyn Flare*  
Register of Deeds Stamp & REGISTER  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William E. Sikkema, in a field survey on 8/15, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1-9, Corner common to Sections 22,23,26,27 of T21N, R7W; Corner set by Deputy Surveyor Colman in 1856 and witnessed by:  
12" Aspen - N77°E - 15 Links                      8" Aspen - S30°W - 5 Links  
Missaukee County Surveyors notes Apr. 25, 1894 in Sec. 26 Witnessed Cor: N42 1/2°E - 12" Yellow Pine - 80 Links  
S33°W - 10" Balsam - 52 Links  
Missaukee County Surveyors Misc. Notes give witnesses: N42 1/2°E - Norway Pine - 80 Links; S54°E - 10" Balsam Fir - 42 Links  
Missaukee County Surveyors notes of June 1910 for Sec. 27, T21N-R7W, call out for N.E. Corner as being found  
stake from bearings, put on N side of stake, pump handle 2 ft long. Witnessed by: N42°E-Cedar Fence Post-59 Links  
Missaukee County Surveyors notes of June 26, 1913, for Sec. 23, T21N-R7W, call out for S.W. Corner as being a stone.  
Witnessed by: S05°W - 12" Corner Fence Post - 44 Links                      N45°E - 9" Corner Fence Post - 60 Links  
Consumers Power Company, F.A.Fisher, a reg. surveyor call out for Sec. 22, SE Cor as found remains of old wood stake  
with stone and iron around it. Tele Pole - NW - 39.3', Tele Pole - NE - 122.9', Fence Cor Post - NE - 38.5'  
Mark Robison, 1995 Certificate of Survey in the SE1/4 of the NE1/4 shows no reference to the corner, per phone call to  
Mark, he found Iron & Cap which he used to establish the N1/4 corner by S. P. Witnessed by: Phone Riser-N35°W-  
44.20'; Phone Riser-S45°W-36.30'; CL-North-1.0'; Fence Post-N45°E-51.41'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-9, Found 1" Pipe 3' below surface of road, 1' South of Centerline East-West, 3' West of Centerline North, appears to be at gravel surface of the old road bed, the pipe fits 2 of Robison's witnesses and agrees with his overall mile distance. Also found bent 1/2" iron approximately 4.5' East. Per phone call to Kelly Bekken the county crushed and shaped the road in 1996 without witnessing any of the corners, it appears that the iron had been moved at this time. This corner is accepted as the best available evidence of the position of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-9  
Raised 1" Pipe with 1/2" by 18" iron and Miss. County Mon., stamped #45505, 1999, in Mo  
Fd Nail in Cedar Fence Post - 51.44' - N35°E  
Set Nail in West Side Power Pole - 150.27' - S05°W  
Set Nail in East Side Mail Box Post - 23.45' - S50°W  
Set Nail in West Side 10" Poplar Tree - 119.08' - N20°E



Signed by William E. Sikkema Date 11/3/99

Surveyor's Michigan License No. 45505

Pear Group Reviewed and Approved  
Date: 12-9-99  
[Signature]  
Dean Geers, Missaukee Co. Representative