

DEC 27 1993

#913

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 439

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>7W</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 16 1993 12:40 PM

Roslyn Flare
REGISTER

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on December 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor
B. Ash 11 N 67 1/2° E 34, B. Ash 9 N 65 1/2° W 19

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13) South Quarter corner of Section 35

Reestablished the South Quarter corner of Section 35 on line and midway between the Southwest corner and Southeast corner of Section 35. Corner falls in swamp ±42' North of East-West fence line and ±22' East of old North-South fence and 20' West of old North-South fence. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13) Set 1/2" x 36" Iron and Missaukee County monument

Corner is in 1-2' of standing water

- S 36° W - 36.20 - Fence post
- S 15° W - 44.92 - Fence post
- S 22° E - 48.20 - Corner fence post
- N 28° E - 59.68 - 12" Double Basswood

Peer Group Reviewed and Approved

Date: 12-15-93
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977

Date 12/15/93