DEC 27 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

LIBER 283 PAGE	438
LIBER LYGE	

Fo	COMMISSION or corners in		Filing Require	ement of Act 74, Mich. P.J	A. 1970	LIBER	<i>800</i>	PAG	<u> </u>		
	Missaukee (County)	_	Located In:	Corner Code ##		MISSAL	JKEE CX	TNUC	Y M	ICHIG/	AN
1.	Public Land Survey		T <u>21N</u> R <u>7W</u> T R T R	K-13		-uxusoso					
	Property Controlling in Section Miscellaneous Property in Sec.	S	TR _TR _TR _TR			ter of Dec					
	Lot No, Re					A B C	D E	F G	H 1	J K	-
in cu Ma ab Co ex	o hereby certify that under requisitions 1 and 2 above were in arrent manual of survey instructionagement or by a decree of a bove were in conformance with burt of Law; established, respressed below:	uirements conforma ctions of t Court of L n the rules e-establish	of P.A. 74, Michigan P.A. ance with regulations and the United States Departament and for that the corners of the Michigan Board of	of 1970, the corner points mentic d rules therefore as required in timent of the Interior, Bureau of L er points mentioned in lines 3, 4 a of Land Surveyors or by a Decree nonumented, recovered, found and range, may be recorded	ened the and nd 5 of a d as	5 6 7 8 19 9	20	21	-15	-14 -14 -23 -26	13-24-25-
141	on this certificate.	71 IIC(3, 81	ii iii tiic same town a	id range, may be recorded		2 31	32	33	-34	-35	36-

- Description of original monument and accessories and/or subsequent restoration:
- K-13) 1837 GLO Section post by John Brink, Deputy Surveyor Hemlock 16 N 30° E 31, Maple 10 N 51 1/2° W 35

K-13) 1893 Beuthien survey in Section 36: Stone, Iron, Crockery
K-13) 1993 Granger survey in Section 35, Liber S-3, pages 181-182: Set 1/2" Iron and cap

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - K-13) Section corner common to Sections 35 and 36

Found Granger Iron of record per Liber S-3, pages 181-182 but it was not utilized in this survey.

Reestablished the Section corner common to Sections 35 and 36 based on a retracement of the 1893 Beuthien survey of Section 36. No physical evidence of the corner was found so the corner position was determined by prorating the recorded Beuthien distances which were consistant throughout the section. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - K-13) Set 1/2" x 36" Iron and Missaukee County monument

Surveyor's Michigan License No. _

Corner falls ±12' West of the centerline of North-South field lane, ±24' North of centerline of East-West field lane.

N 71° E - 29.87 - 20" Dogwood	P
S 75° E - 44.47 - Corner fence post	Da
S 69° E - 28.46 - 12" Dogwood	
S 20° E - 35.93 - 14" Dogwood	٦.
S 39° W - 65.22 - 10" Poplar	
S 15°E - 73.59 - Granger Iron	

eer Group Reviewed and Approved

Dean Geers, Missaukee Co. Representative

_ Date __12/15/93