

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 308 PAGE 717

1086

For corners in
Missaukee
(County)

Located in:

Corner Code #

- | | | | | | |
|---|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>21N</u> | R | <u>7W</u> | <u>M-8</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous
Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 20 1996** 9:45 A.M.

Paula Flare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-8) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Sugar 10-S9W-30; Sugar 9-N40W-32
- M-8) 1985 Wilcox LCRC, Liber 1, pg. 701; Set 1/2" Iron and Cap midway and on line between the section corners one half mile to the North and South, N50E-50.20-20" Apple; N35W-49.06-3" Cherry; N50W-127.95-P.P.; West-36.30-Corner fence
- M-8) 1988 Wade-Trim/Granger Survey, Liber S-2, pg. 405; Found Iron and Cap, North - "T" Iron - 29.91; East - Gate Post - 35.85; West - Fence Post - 85.25; N30E - 3/4" Pipe - 47.40

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-8) Corner Common to Section 24, T21N, R7W and Section 19, T21N, R6W, Found Iron with Cap #14102 of record on Centerline Road North and South, on fence line to the East, 6'± Southerly of fence line to the West. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8) Set Missaukee Co. Mon. on existing iron in mon. box
N50E - 50.62 - 20" Apple
S85E - 36.14 - Corner fence post
N80W - 60.64 - Cut off P.Pole
North - 29.91 - "T" Iron

Peer Group Reviewed and Approved

Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____
Surveyor's Michigan License No. 33977

Date 12-19-96

