

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 308 PAGE 718

1087

For corners in Missaukee (County) Located In: Corner Code #

1. Public Land Survey	T	21N	R	7W	M-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 20 1996 2:45 P.M.

Paula K. Lane
REGISTRAR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-9) 1837 GLO Section Post by John Brink, Deputy Surveyor; Beech 11-S5W-25; Beech 10-N25W-35
- M-9) 1890 County Survey in Section 30, T21N, R6W; Pint Blue glass bottle with stones around it, 18" below surface
- M-9) 1985 Wilcox Associates LCRC, Liber 1, pg. 701; Found 3/4" round head bolt in Centerline Roads, S25E-68.35 - NW top cor transfer box, N40E - 45.33 - Cor Fence post, S75W - 111.47 - 48" Maple, S30W - 71.61 - 10" Box Elder

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-9) Corner Common to Sections 24 and 25, T21N, R7W and Sections 19 and 30, T21N, R6W, Reset corner by using the quarter corner and section corner to the North based on the previous survey using these corners. Corner is in centerline of intersection. This corner is accepted as the best available evidence the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9) Set Missaukee Co. Mon. on 1/2" Iron in Mon. Box
 - N28E - 48.33 - Set Wit. Iron
 - N12W - 58.98 - Set Wit. Iron 1' East of stop sign
 - S 15E - 55.95 - Set Wit. Iron 2' West of stop sign
 - S 85W - 111.34 - 5" Maple

Peer Group Reviewed and Approved

Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by _____ Date 12-19-96
Surveyor's Michigan License No. 38977