

MAY 28 1997

COMMISSION

LIBER 308 PAGE 719

#1088

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields: For corners in Missaukee (County), Located In: Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Section

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 20 1996
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- M-10) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Sugar 10-S56W-18; Sugar 9-N20 1/2W-32
M-10) 1890 County Survey in Section 30, T21N, R6W; Corner was used but no wit's recorded

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-10) Corner Common to Section 25, T21N, R7W and Section 30, T21N, R6W. This corner was reestablished midway and on line between the section corner one half mile to the North and South. This position also fits very well with the County Survey information recorded in Section 30, T21N, R6W. The corner is ±8' West of the centerline of North-South road and on fence lines to the West and East. This corners is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10) Set Missaukee Co. Mon. on 1/2" Iron in Mon. Box
S50W - 54.18 - Power Pole
N30W - 38.05 - Corner Fence Post
S 64E - 27.86 - Set Wit. Iron
N 66E - 45.56 - Set Wit. Iron.



Signed by [Signature] Date 12-19-96
Surveyor's Michigan License No. 33977