

MAY 28 1997

LIBER 308 PAGE 720

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

# 1089

Form with fields: For corners in Missaukee (County), Located In: 21N R7W, Corner Code # M-11. Includes sections for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 20 1996
Signature: Carolyn F. Lane
REGISTER
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numerical data points for survey locations.

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-11) 1837 GLO section post by John Brink, Deputy Surveyor; Sugar 10-S32W -22; Beech 8-N47W-42
M-11) County Survey Notes, SE corner Section 25; Stone/Iron, Stone Bldg - S52W-49.3
M-11) 1890 County Survey in Section 30, T21N, R6W; Stone, Corner of Stone Bldg - S45W-67 1/2
M-11) 1893 County Survey in Section 36, T21N, R7W; Stone, Stone Bldg - S45W - 67 1/2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11) Corner common to Sections 25 and 36, T21N, R7W and Sections 30 and 31, T21N, R6W; Found angle iron 3'± Easterly Centerline Road North and South, 1'± Southerly Centerline Road to West, 2'± Northerly Centerline Road to East. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11) Set 1/2" Iron with Missaukee Co. Mon. in mon. box
N35E - 42.13 - Set Wit. Iron
S35E - 40.42 - Found Nail NE side of P.Pole
S65W - 45.07 - Found Nail NW side of P.Pole
N50W - 67.83 - Found Nail 36" Cottonwood

Signed by [Signature]
Surveyor's Michigan License No. 33875

Date 12-19-96