

SURVEY & REMONUMENTATION

DEC 21 1993

903

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 346

For corners in **MISSAUKEE COUNTY**

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 13 1993 11:30 AM

Paulyn Flare
REGISTER

Register of Deeds Stamp & File Number

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>7W</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, J. Dean Geers, in a field survey on December 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-13) 1837 GLO Section post by John Brink, Deputy Surveyor
Beech 10 N 23° E 25, Beech 0 N 31 1/2° W 56
- M-13) 1893 Beuthien survey in Section 36: Corner was used but no information given
- M-13) Beuthien Notes, Southeast corner of Township: Beech 10 N 23° E 25, Beech 9 N 31 1/2° W 56
- M-13) 1989 D. Porter Survey: Found wood stake and channel Iron 4' below grade, raised with Iron and cap

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-13) Section corner common to Section 36, T21N, R7W and Section 31, T21N, R6W
Found Porter Iron. Corner falls ±6' West of centerline of road to North, ±2' South of centerline of road to East and ±2' North of centerline of road to West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-13) Found 1/2" Iron: Set monument box and added Missaukee County monument to Iron
S 01° W - 19.05 - Set pk nail in West end of culvert
N 87° E - 77.18 - Set pk nail in North end of culvert
N 63° E - 48.77 - Road sign post
N 58° W - 63.08 - Top center of phone pedestal

Peer Group Reviewed and Approved
 Date: 12/8/93
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/8/93
 Surveyor's Michigan License No. 33977