

**SURVEY &
REMONUMENTATION**

#944

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 290 PAGE 21

COMMISSION

For corners in

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED **OCT 28 1994** ^{1:15} P.M.

Paulyn Flare
Register

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, J. Dean Geers, in a field survey on October 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-9) 1853 GLO Quarter Section post by John Brink, Deputy Surveyor
Beech 13 S 30 E 35, Hemlock 18 N 66 1/2 E 12
- B-9) 1893 Beuthien Survey in Section 19: Corner was used for Section break down but no witnesses were given
- B-9) 1897 Beuthien Survey in Section 30: Iron post, Corner fence post S 40 1/2 E 61, Maple 4 S 56 W 72

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-9) Section corner common to Sections 19 and 30

Found 1" pipe in monument box in the centerline of the East-West road and in the centerline of the road to the North. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-9) Set 1/2" Iron and Missaukee Co. monument in monument box

- S 38 E - 136.20 - Northwest corner of house
- S 25 E - 112.79 - 20" Maple
- S 60 W - 163.39 - Power pole
- S 43 W - 48.06 - 1/2" Iron

Peer Group Reviewed and Approved

Date: 10-26-94

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers*

Date 8/8/94

Surveyor's Michigan License No. 33977