

JUN 02 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 576

917

For corners in

Table with columns: Missaukee (County), Located In: (T, R, S, N, W), Corner Code #. Row 1: Public Land Survey, T 21N R 8W, C-13.

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 21 1993 12:30 M

Handwritten signature: Carolyn Flare REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, J. Dean Geers, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13) 1837 GLO Section post by John Brink, Deputy Surveyor Beech 11 N 77° W 05, Hemlock 16 N 70° E 42

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13) Reestablished the Section corner common to Sections 31 and 32 on line and at proportional distance between the Southwest corner of Section 31 and the South Quarter corner of Section 32. Corner falls in old fence line to the North, ±33' North of East-West fence line and ±14' North of centerline of two-track. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13) Set 1/2" x 36" Iron and Missaukee County monument

- N 09° W - 4.15 - 4" Cherry
N 25° E - 28.37 - 3" Maple
East - 46.91 - 8" Maple
S 10° W - 32.20 - 40" Twin Maple

Peer Group Reviewed and Approved

Date: 12/20/93
J. Dean Geers, Missaukee Co. Representative

Signed by [Signature]

Date 12/17/93

Surveyor's Michigan License No. 33977

Grid table with columns A-L and rows 2-13. A dot is marked at row 10, column C.