

**SURVEY &
REMONUMENTATION**

#946

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 390 PAGE 23

For corners of **COMMISSION**

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED **OCT 28 1994** 1:15 PM

Paulyn Florie
REGISTERED

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on October 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-9) 1853 GLO Quarter Section post by John Brink, Deputy Surveyor
Beech 16 N 3 3/4 W 18, Beech 12 N 64 W 20
- D-9) 1899 Cavanagh Survey in Section 29: Corner was used but no witnesses given
- D-9) 1909 Cavanagh Survey in Section 20: Maple 6 S 58 E 36 1/2, Maple 4 S 63 1/2 W 32 1/2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-9) Section corner common to Sections 20 and 29
Found 1" pipe over Iron bar
Corner is 1' South of East-West centerline. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-9) Set 1/2" Iron and Missaukee Co. monument in monument box

- N 04 E - 40.57 - Set Iron
- S 02 E - 66.55 - Set Iron
- S 60 W - 130.96 - Power Pole
- S 35 W - 31.87 - Pk-nail in West end CMP
- S 36 E - 35.62 - Pk-nail in East end CMP

Peer Group Reviewed and Approved

Date: 10-26-94
J. Dean Geers, Missaukee Co. Representative



Signed by J. Dean Geers

Date 8/8/94

Surveyor's Michigan License No. 33977