

JUN 02 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 575

914

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 21 1993 12³⁰ M.

Paulyn Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, J. Dean Geers, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor
Beech 10 N 7° W 38, Elm 7 N 67° E 44
- D-13) 1909 Beuthien survey in Section 32: Corner was used for section breakdown, stake with crockery and iron, Elm 12 N 10 3/4° W 104, Clump Cherries N 31° E 67 1/2
- D-13) 1991 Erickson survey, Liber S-3, page 170: Found 1" pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13) South Quarter corner of Section 32
Found 1" pipe which had been removed.

Reset pipe from witness per Erickson survey in Liber S-3, page 170. Corner falls ±5' North of centerline of East-West two-track. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13) Reset 1" pipe and added 1/2" x 36" Iron and Missaukee County monument
N 22° W - 33.79 - 4" Cherry
N 15° E - 57.05 - 7" Cherry
S 67° E - 97.50 - 9" Elm
S 20° W - 28.67 - 8" Stump
S 45° W - 35.82 - 8" Cherry

Peer Group Reviewed and Approved

Date: 12-20-93
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/17/93

Surveyor's Michigan License No. 33977