

DEC 27 1993

909

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 435

For corners in

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 8W	E-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 16 1993 12:40 P.M.

Paulyn Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-13) 1837 GLO Section post by John Brink, Deputy Surveyor, Sugar 22 N 50° E 14, Sugar 20 N 49° W 20
- E-13) Beuthien survey notes: Stone, plow point: large stone N 74° W 38
- E-13) 1909 Beuthien survey in Section 32: Corner was used for section breakdown, iron pipe 3' long, F.P. Northeast 52', corner fence post Northwest 48', corner barnyard post Southwest 72'
- E-13) 1983 McClung L.C.R.C., Liber 1, page 688, Found 1" pipe at road intersection; no witnesses given
- E-13) 1985 Jerry Wilcox L.C.R.C., Liber 1, page 704, Found 1 1/4" pipe in centerline of road to North, ±3' South of centerline East-West, N 9° W Power pole 111.48, S 35° E Power pole 59.14, S 1° W Northeast corner barn 75.67, S 65° W corner fence post 53.15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13) Found 1 1/4" pipe ±4' Southerly of centerline roads East-West and in centerline of road to North. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13) Replaced found 1 1/4" pipe with 1/2" x 36" Iron and Missaukee County monument
 - S 35° E - 59.15 - Power pole
 - S 01° W - 75.64 - Northeast corner barn foundation
 - S 65° W - 53.32 - Pasture fence post
 - N 62° E - 57.78 - Center of Top of telephone riser

Peer Group Reviewed and Approved

Date: 12-15-93

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/15/93

Surveyor's Michigan License No. 33977