

SURVEY & REMONUMENTATION

#948

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 390 PAGE 25

For corners in **COMMISSION**
Missaukee
(County)

Located In: Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>21N</u> R <u>8W</u> | <u>F-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

MISSAUKEE COUNTY MICHIGAN

RECORDED **OCT 28 1994** 1:15 P.M.

Caslyn Flare
REGISTER

Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on October 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-9) GLO Quarter Section post by John Brink, Deputy Surveyor
Sugar 16 N 17 E 28, Sugar 18 S 40 E 27
- F-9) 1899 Beuthien Survey in Section 28: Cedar stake 2' long; large stone S 63 1/2 W 98
- F-9) 1977 M. McClung LCRC Liber 1, Page 516: Found Iron in monument box; No witnesses given
- F-9) 1982 J. Wilcox, LCRC Liber 1, Page 674: Found 1 1/4" pipe in monument box
- F-9) 1985 J. Wilcox, LCRC Liber 1, Page 703: Found 1 1/4" pipe in monument box


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-9) Section corner common to Sections 21 and 28
Found 1 1/4" pipe of record (Liber 1, Page 703) in centerline intersection. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-9) Set 1/2" Iron and Missaukee Co. monument in monument box
S 38 E - 58.39 - Corner fence post
S 28 E - 70.65 - South sign post
N 49 W - 146.58 - 24" Locust
S 33 W - 67.62 - Set Iron @ South end Tele pedestal

Peer Group Reviewed and Approved
Date: 10-26-94
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers* Date 8/8/94
Surveyor's Michigan License No. 33977