

DEC 27 1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 434

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 16 1993 12:40 PM

Paulyn Flare
REGISTRAR

Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor
Lynn 8 N 36° E 06, Beech 12 N 45° W 12
- F-13) 1909 Beuthien survey in Section 33: Buried a piece of plow point beside post,
Sugar 6 N 23 1/4° E 73 3/4
- F-13) 1982 Jerry Wilcox L.C.R.C., Liber 1, page 674, Found pk-nail in centerline of road
- F-13) 1983 McClung L.C.R.C., Liber 1, page 688, set 5/8" Iron
- F-13) 1985 Jerry Wilcox L.C.R.C., Liber 1, page 704, reset 1/2" Iron and cap based on McClung survey of record, Liber 1, page 688

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-13) Found 1/2" Iron & cap #14102 in monument box, ±2' Northerly of centerline of road East-West and ±5' Easterly of centerline of road Northerly. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13) Replaced found 1/2" Iron with 1/2" x 3/8" Iron and Missaukee County monument in monument box
N 48° W - 112.64 - Face of light pole
S 60° E - 125.21 - 10" Red Pine
N 30° E - 77.56 - Power pole
S 13° W - 30.47 - Set 1/2" Iron and cap

Peer Group Reviewed and Approved

Date: 12-15-93

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/15/93
Surveyor's Michigan License No. 33977