

SURVEY & REMONUMENTATION

949

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 290 PAGE 56

For corners in **COMMISSION**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED **OCT 28 1994** ^{1:15} PM

Roslyn Flors
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on October 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-9) 1853 GLO post by John Brink, Deputy Surveyor
Sugar 12 N 75 3/4 W 38, Sugar 16 N 50 3/4 E 21
- G-9) 1894 Beuthien Survey in Section 27: Iron Post; Beech 8 S 73 1/2 E 109'
- G-9) 1899 Beuthien Survey in Section 28: Cedar stake and broken glass; No witnesses given
- G-9) 1977 M. McClung LCRC Liber 1, Page 516: Found Iron in monument box; No witnesses given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-9) Section corner common to Sections 21, 22, 27 and 28
Found 3/4" pipe in monument box in centerline intersection. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- G-9) Set 1/2" Iron and Missaukee Co. monument in monument box

S 82 W - 169.60 - P. Pole
N 22 W - 85.18 - 6" Maple
N 40 W - 58.95 - 6" Willow
N 15 W - 116.32 - 8" Maple (nail pulled)
S 38 E - 50.00 - Set 1/2" Iron

Peer Group Reviewed and Approved

Date: 10-26-94

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers*

Date 8/8/94

Surveyor's Michigan License No. 33977