

**SURVEY &
REMONUMENTATION**

950

DEC 07 1994

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 290 PAGE 27

For corners in **COMMISSION**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED OCT 28 1994 1:15 PM

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on October 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9) GLO Quarter Section Post by John Brink, Deputy Surveyor
Cedar 8 N 31 1/2 W 20, Tamarack 13 S 71 1/2 E 26

H-9) 1894 Beuthien Survey in Section 27: Corner was used but no witnesses given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9) Section Corner common to Sections 22 and 27

Found Iron and cap #14102 in centerline of East-West Rd. and in line with fence line to the South. Corner was reestablished midway and on line between the Section corners to the West and East. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


H-9) Set 1/2" Iron and Missaukee Co. monument in monument box

- S 35 E - 48.93 - 6" Elm
- N 02 E - 46.26 - 8" Willow in clump
- N 30 W - 61.15 - 8" Elm
- N 37 E - 51.99 - Set 1/2" Iron on South side of phone riser

Peer Group Reviewed and Approved

Date: 10-26-94

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977

Date 8/8/94