

DEC 27 1993

#905

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 283 PAGE 431

For corners in

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 16 1993 12:40 PM

Roslyn Flare
REGISTER

Register of Deeds Stamp & File Number

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 8W	J-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor
Sugar 12 N 20° W 26, Beech 8 N 38 1/2° E 23

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13) South Quarter corner of Section 35
Found 1 1/4" pinched pipe ±2' Southerly of centerline of road East-West and in line with fence line North. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13) Replaced found 1 1/4" pinched pipe with 1/2" x 36" iron and Missaukee County monument in monument box
N 5°E - 31.52 - Corner fence post
N 62° W - 75.24 - Face of fiberglass fence post
N 51° E - 40.64 - Set Iron/cap
S 5° W - 33.58 - Set Iron/cap

Peer Group Reviewed and Approved
Date: 12-15-93
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/15/93

Surveyor's Michigan License No. 33977