

DEC 21 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

902

LIBER 283 PAGE 345

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 13 1993 11:30 AM

Ruby Flare
Recorder

Register of Deeds Stamp & File Number

For corners in

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 8W	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, J. Dean Geers, in a field survey on December 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- L-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor
Maple 13 N 41° E 13, Maple 13 N 32° W 37
- L-13) 1893 Beuthien survey in Section 36: Stone, fence post North 51 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13) South Quarter corner to Section 36:

Found 4" x 10" piece of pipe over Northwesterly corner of an 8" rectangular flat stone ±2' below the road surface. The corner is ±9' South of centerline of East-West road and ±1' East of fence line to North. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13) Replaced Found 4" piece of pipe with 1/2" x 36" Iron and Missaukee County monument
Corner is ±6" below grade

- N 03° E - 41.17 - Corner fence post
- N 45° W - 63.93 - Fence post
- N 31° W - 49.80 - Fence post
- S 09° W - 16.82 - Set Iron at back of ditch opposite fence line to North

Peer Group Reviewed and Approved

Date: 7/11/93

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*

Date 12/8/93

Surveyor's Michigan License No. 33977