

**SURVEY &  
REMONUMENTATION**

LIBER 291 PAGE 415

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

966

For corners **COMMISSION**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 23 1995 <sup>11:42</sup> A.M.

*Carolyn Flare*  
REGISTRAR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-2) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor, Cedar 14" diameter quarter section corner
- M-2) 1889, 1914, 1917 Beuthien surveys: Corner was used for various surveys, corner fence post West 50'
- M-2) 1928 MDOT Plans, Project #057-16, File #J-17-A-6: no corner indicated
- M-2) 1988 Wilcox survey, unrecorded: Reestablished corner by retracement of Beuthien survey of Section 6, T21N, R7W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2) Quarter section corner common to Section 1, T21N, R8W and Section 6, T21N, R7W.  
Found 1/2" Iron and cap per 1988 Wilcox survey. Corner is ±1' West of Centerline of North-South road. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2) Set 2 1/2" brass Missaukee County monument on existing 1/2" Iron in monument box  
S 66° W - 71.67 - Set nail in 6" Twin Poplar  
N 56° W - 63.45 - Set nail in 2" Willow  
N 73° E - 69.79 - Found nail in 6" Poplar  
S 87° E - 69.85 - Set nail in 6" Poplar

Peer Group Reviewed and Approved  
Date: 11-30-94  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/13/94  
Surveyor's Michigan License No. 33977