

**SURVEY &  
REMONUMENTATION**

LIBER 291 PAGE 408

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

961

For corner **COMMISSION**

Missaukee  
(County)

Located In:

Corner Code M-7

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>21N</u> R <u>8W</u> | <u>M-7</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 23 1995 11:47 AM

*Paulyn Flare*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, J. Dean Geers, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-7) 1837 GLO Section post by John Brink, Deputy Surveyor  
Beech 10 S 26° W 33, Birch 8 N 47 1/2° W 34
- M-7) 1894 Beuthien survey: White Pine stump 40 N 74° W 15
- M-7) Beuthien Notes: Corner fence post N 44° W 73
- M-7) 1929 MDOT Plans, Project #057-16, File #J-17-A-6: Spike in Cedar post, no permanent witnesses given
- M-7) 1971 Wilcox survey, unrecorded: Found Pk nail in center of intersection  
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-7) Section corner common to Sections 13 & 24, T21N, R8W and Sections 18 & 19, T21N, R7W

Found Pk nail reset per 1981 survey. Corner is in Centerline of North-South road, and ±2' North of Centerline of East-West road. This corner is accpeted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-7) Set 2 1/2" brass Missaukee County monument on 1/2" Iron in monument box

S 58° W - 101.33 - Set nail in 10" White Birch  
N 43° W - 43.30 - Set Pk nail in North end of CMP  
S 51° W - 39.58 - Set Pk nail in South end of CMP  
S 52° E - 107.95 - Set nail in 8" White Pine

Peer Group Reviewed and Approved

Date: 12-7-94

*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/13/94

Surveyor's Michigan License No. 33977