

**SURVEY &  
REMONUMENTATION**

LIBER 291 PAGE 401

954

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

MISSAUKEE COUNTY MICHIGAN

RECORDED ~~JAN 23~~ 1995 11 47 AM

*Paulyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

Missaukee <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, J. Dean Geers, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-12) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor  
Cedar 9 S 66° W 20, B. Ash 10 N 17 1/2° W 42
- M-12) 1986 McClung Survey; Liber S-2, page 312: No corner found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12) Quarter Section corner common to Section 36, T21N, R8W and Section 31, T21N, R7W

Reestablished corner equidistant and on line between the section corner to the North and South. Corner is in centerline of North-South road and ±9' North of trail road to the West. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12) Set 2 1/2" brass Missaukee County monument on 1/2" Iron in monument box

- N 75° E - 37.40 - Set nail in top of fence post
- S 60° E - 39.06 - Set nail in top of fence post
- N 67° W - 32.58 - Set nail of power ppole
- S 64° W - 52.45 - Set nail in 10" Poplar

Peer Group Reviewed and Approved

Date: 12-21-94

*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by \_\_\_\_\_ Date 12/13/94

Surveyor's Michigan License No. 33977