

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 22 N.R. 5 W


Missaukee COUNTY

DESCRIPTION OF CORNER Sec. corner common to Sections 23-24-25-26

CORNER MONUMENT Cons. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 11/17/67

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" J. Pine S 10 E 32.6'

7" J. Pine S 80 W 38.8'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during a survey of Section 26. Set corner on line over 1/4 and section corner east, at proportionate measurement for longitude. This checks measurement to section corners north and south, and to identifiable physical features south and east. Nothing found for evidence of a previous corner. Falls north and east of fence intersection, but fences found to be highly unreliable in this township.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Oetting* DATE 11/20/67  
REGISTERED LAND SURVEYOR #10068