

Handwritten notes at top left.

JAN 19 2000

LIBER 333 PAGE 429

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1341

For corners in

Table with columns: Missaukee County, Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 09 1999 4:20 PM

Handwritten signature: Carolyn Flare REGISTER

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, J. Dean Geers, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of survey notes and monuments including E-13) 1837 GLO Section Post by John Brink, Deputy Surveyor. 10" Hemlock-N54 1/2 E-43 lks, 11" Hemlock-N43 1/2 W-26 lks. E-13) 1852 GLO Section Post recovered by A. Curtis, Deputy Surveyor. 12" Hemlock-S30E-9 lks, 16" Hemlock-S65W-66 lks. E-13) 1912 Beithien Survey; WPS 20"-N6W-93 lks, WPS 20"-N24W-78 lks. E-13) 1914 Beuthien Survey; Cedar stake and stone. White Pine stump-N6W-93 lks, White Pine stump-N24W-78 lks. E-13) 1914 Beuthien Survey; Cedar 4X4 stake. White Pine stump-N6W-93 lks, White Pine stump-N24W-78 lks. E-13) 1915 Beuthien Survey; No corner witnesses given. E-13) County Survey Notes: 12" Hemlock-S30E-9 lks, 16" Hemlock-S65W-66 lks. E-13) 1938 Schaaf Notes: Found post. Set monument. E-13) 1972 McClung LCRC; Liber 1, Page 89, Found 1 1/2" pipe. Power pole-N45E-68.6', Maple clump-S30E-57.8' E-13) 1974 Higgins Survey, S-1, Page 188; Found 1 1/2" pipe. E-13) 1979 McClung Survey, S-1, Page 496; Found 1 1/2" pipe. Power pole-N45E-68.6', Maple clump-S30E-57.8' E-13) 1987 Roser LCRC, Liber 1, Page 799; Found 1 1/2" pipe. Power pole-N45E-69.03', 10" Maple clump-S30E-57.10', Corner fence post-N40W-48.66', Cedar Post-S45E-47.50'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13) Section corner common to Section 32 and 33, T22N, R5W and Section 4 and 5, T21N, R5W. Found 1/2" rebar at surface and 1 1/2" pipe +/- 1.5' deep surrounded by several cobble stones. Corner is in centerline of East-West Road and +/- 1.5' East of centerline Road North-South. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13) Found 1/2"x18 rebar over 1 1/2" pipe. Pulled 1/2" rebar and drove 5/8" rebar into pipe and set Missaukee County Monument.

Table with columns: Bearing, Distance, Description. Includes entries for N53E 68.98' Set nail in southeast face of powerpole, N13W 97.32' Set nail in east face 6" oak, S24W 126.69' Found nail in east face 12" twin oak, S13E 130.20' Set nail in west face 5" oak, N40W 48.62' Found spike in northeast face Corner fence post

Peer Group Reviewed and Approved

Date: 12-9-99
J. Dean Geers, Missaukee Co. Representative



Signed by [Signature]
Surveyor's Michigan License No. 33977

Date 11-23-99