

JAN 19 2000

LIBER 333 PAGE 431

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

#1343

Table with columns: Missaukee County, Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 09 1999 4:00 PM

Signature of Register: Carolyn Flare

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, J. Dean Geers, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of survey points and monuments including G-13) 1837 GLO Section post by John Brink, Deputy Surveyor, 11" Hemlock-N35E-84 lks, 16" Yellow Pine-N36W-5 lks, etc.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13) Section corner common to Section 33, T22N, R5W, Section 34, T22N, R5W, Section 3, T21N, R5W and Section 4, T21N, R5W. Found 5/8" rerod as recorded in Liber 1, Page 801.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13) Found 5/8" rerod and added Missaukee County Monument. S32W 31.12' Set nail in East face 8" J. pine, N60E 52.23' Found nail in West face 8" J. pine, etc.

\*Previous Witness



Peer Group Reviewed and Approved

Date: 12-9-99 J. Dean Geers, Missaukee Co. Representative

Signed by [Signature] Surveyor's Michigan License No. 33977

Date 11-23-99