

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>22N</u>	R	<u>5W</u>	<u>J9</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	T	R	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	T	R	_____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Feb. 8, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9										●			
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J9 – **1852** – GLO – A. Curtis – Set ¼ Post  
Tamarack 7" N10°W 105 L.  
Tamarack 7" S15°E 104 L.  
- **1916±** - CSR – Bk. 21, p. 34 –  
¼ S. in Wet Marsh nothing to bear to.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J9 – ¼ Corner common to Section 23 & 26 – Searched in open grass marsh for post. Water 2 to 3'± deep. Couldn't find any evidence of post or BT's per GLO and CSR. Set 4" DNR Alum. Cap on 1" x 8' long galv. iron pipe by single proportion to GLO between found DOC (DNR) Monuments at 'I-9' and 'K-9'. Measured West 96'± 10' vs. 56' – GLO to edge of marsh. DNR Mon. accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J9 – Stamped 4" DNR Alum. Cap on 1" x 8' long galv. iron pipe.  
Set Blue Carsonite Post 1' N.  
S32°E 79.24' to set Nail & Tag in NE side 17" R. Pine scribed 'XBT'  
S75°W 119.50' to set Nail & Tag in S. side 13" J. Pine scribed 'XBT'  
N68°W 149.70' to set Nail & Tag in SW side 10" J. Pine scribed 'XBT'  
S60°E 64.19' to set Nail & Tag in NE side 3" R. Pine



Signed by: Craig W. McVean Date: 12/18/2007  
Surveyor's Michigan License No.: 39088