

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

| For Corners In: Missaukee (County) | Located In | Corner Code # |
|--|--------------------------------------|---------------|
| 1. Public Land Survey | T <u>22N</u> R <u>5W</u> | <u>J10</u> |
| 2. Property Controlling in Section | S <u>35</u> T <u>22N</u> R <u>5W</u> | <u>1</u> |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 23, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

J10 - None

- 1 - **1913 & 14** - CSR - E. A. Beuthien - Sec. 35 - Petition survey
- Cedar stake, WPS N1½°E 42
- **1967** - DNR Survey Map - K. J. Ostling
- Set 1" x 24" pipe; BT 8" W. Pine N60°E 3.6';
- BT 6" Spruce S70°W 2.2'.
- **2003** - Unrecorded Survey - North Central Survey Inc. -
- Proj. # 03065 - L. L. Cavanagh - Fd. ¾" pipe.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J10 - C ¼, Section 26 - Set 2" Alum. Cap on 5/8" x 34" rebar at intersection of ¼ line per Standard BLM procedure.

- 1 - W 1/16 Common to Sec. 26 & 35, T22N, R5W - Dug 9' E & W x 7' N-S area in swamp based on retracement of Beuthien survey but couldn't find cedar stake. No conclusive evidence of Beuthien's BT. Set 2" Alum. Cap on 5/8" x 5' iron rebar per Standard BLM procedure in dug area.

Ref. Pt. - Fd. 1" iron pipe per Ostling and used by Cavanagh is S84°52'E 14.58' of '1'. Could not accept Ostling pipe since it is based on rejected position at 'J11', 1" pipe not utilized as '1' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J10 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
Set Blue Carsonite Post with loc. tag 1' NE
S24°E 13.59' to set nail and tag in E. side Tw. 10" R. Maple scribed 'XBT'
S70°W 42.78' to set nail and tag in S. side 10" W. Pine scribed 'XBT'
N08°W 30.77' to set nail and tag in W. side Tw. 10" R. Maple scribed 'XBT'.
N29°E 48.08' to set nail and tag in SE side 14" W. Pine scribed 'XBT'.

- 1 - Stamped 2" Alum. Cap on 5/8" x 5' iron rebar.
Set Blue Carsonite Post with loc. tag 1' NE
N10°W 31.01' to set nail and tag on W. side 18" W. Pine
N86°E 17.90' to set nail and tag on N. side 15" W. Pine (KJO)
S36°E 27.22' to set nail and tag on E. side 6" R. Maple
N65°W 11.28' to set nail and tag on E. side 6" R. Maple
S84°52'E 14.58' to Ref. Pt. - 1" iron pipe

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 12/18/2007

