

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Missaukee Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T	<u>22N</u>	R	<u>5W</u>	K12
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	T	R	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	T	R	_____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Oct. 16, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35	●	36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K12 – 1852 – GLO – A. Curtis – Set ¼ Post  
 B. Ash 8" N40°E 4 L.  
 B. Ash 6" S60°W 17 L.  
 - 1907 – CSR – Old Cedar stake 4 x 4  
 Hemlock 10" S55½°E 11 L.  
 - 1913 – CSR – E. A. Beuthein – stake; W. Pine 40" N40°E 16  
 - 1967 – K. J. Ostling – DNR Surveyor, LCRC # 484. Set  
 Cons. Dept. mon. from probably Beuthein witness stump,  
 the only one possible in this area.

Could not find post bottom but feel this location conforms to Beuthein record and has to be the position established in 1909 survey.  
 16" Elm N83°W 4.7'; 7" Ash N85°E 26.3'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K12 – ¼ Corner common to Sections 35 & 36, T22N, R5W - Found 4" Aluminum Dept. of Cons. Monument (DNR) and 3.5' long wood guard post scribed 'S35, S36' lying alongside. Monument fits apparent rotten stp. remains of Beuthein's 40" W. Pine witness. GLO and Ostling's witnesses are gone. No evidence of CSR Hemlock BT. Dept. of Cons. Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K12 – 4" Aluminum Dept. of Cons. Cap on 1" galv. iron pipe  
 S79°W 62.00' to set N & T in N. side 9" Cedar scribed 'XBT'  
 S10°W 7.52' to fd. nail in NW side 14" Basswood in clump of 4  
 S76°E 42.56' to set N & T in S. side 6" Fir scribed 'XBT'  
 N45°W 10.73' to fd. nail in W side 7" Ash  
 N44°E 41.99' to fd. nail in NW side 8" Fir scribed 'XBT'  
 East 30.23' to fd. nail in S. side 9" Ash  
 Set Blue Carsonite Post 1' North



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 12/18/2007