

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In _____ Corner Code # _____
(County)

1. Public Land Survey	T	<u>22N</u>	R	<u>5W</u>	<u>L9</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No: _____ Recorded Plat: _____
5. Private Claims: _____

I, Craig W. McVean, in a field survey on March 8, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9											●	
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L9 – 1852 – GLO – A. Curtis – Set ¼ Post
W. Pine 16" N12°W 19 L.
Cedar 12" S45°E 32 L.
- 1916 – CSR – FB. 21, p. 34 – East 39.80
Fd. old ¼ S. Nothing to bear to

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L9 – ¼ Corner common to Sec. 24 & 25 – Could not find evidence of GLO post or BT's. Set 4" DNR Alum. Cap on 1" x 6' long galv. iron pipe single proportion to GLO between section corner ½ mile E & W. Found remains of E-W wolver wire fence is 62'± South. Monument in Tag Elder swamp. Measured grid distance East 2618.58' (2648.58' – GLO, 2633.4' – CSR) and West 2618.58' (2648.58' – GLO, 2626.8' – CSR). Measured East 780'± vs. 801' GLO to edge of swamp. DNR Mon. accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L9 – 4" DNR Alum. Cap on 1" x 6' long galv. iron pipe
Set Blue Carsonite Post 1' N.
N60°W 30.06' to set Nail and Tag in NE side 5" W. Birch scribed 'XBT'
S17°W 35.18' to set ½" x 18" rebar
S60°E 34.58' to set ½" x 18" rebar
N60°E 72.57' to set N & T in SE side 15" Poplar



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 12/18/2007