

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In _____ Corner Code # _____
(County)

1. Public Land Survey T 22N R 5W L11
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Nov. 13, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11											●		
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L11 - 1852 - GLO - A. Curtis. Set 1/4 Post
Cedar 10" N40°E 19 L.
Cedar 12" S35°W 35 L.
- 1913 - CSR - 4" x 4" x 30" Cedar stake.
Gov't witness on Cedar stub S35°W 35 L.
- 1967 - Ken J. Ostling, DNR Surveyor Land Corner Record #483
Set Dept. mon from probable USBT stumps, remains of both in place, with possible evidence of upper face on BT to SW.
Checks swamp edge east.
10" R. Pine N09°E 63.1'
7" Cedar East 26.4'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L11 - 1/4 Corner common to Sections 25 & 36, T22N, R5W - Found 4" Aluminum Dept. of Conservation monument and rotten Cedar post scribed 1/4 on South side. Fit one Ostling living BT and stp. of the other. GLO BT's are now gone. Dept. of Conservation monument accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L11 - 4" Aluminum stamped Dept. of Conservation cap on 1" galv. iron pipe.
S35°W 23.53' to set N & T in W. side 5" Fir
N52°W 32.11' to set N & T in SW side 9" Red Maple
N19°E 74.25' to set N & T in E. side 11" Oak
East 26.49' to set N & T in N. side 12" Cedar (KJO)
Set Blue Carsonite Post 1' North



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 12/18/2007